

COOPER & DUNHAM LLP  
1185 Avenue of the Americas, New York, NY 10036  
(212) 278-0400

Date: January 25, 1999  
Atty Docket No. 7217/57620

TO THE ASSISTANT COMMISSIONER FOR PATENTS  
Washington, D.C. 20231

Sir:

With reference to the filing in the United States Patent and Trademark  
Office of an application for patent in the name(s) of:

Chiharu Hirono

entitled: INFORMATION DISPLAYING SYSTEM, INFORMATION PROVIDING APPARATUS,  
AND INFORMATION PROVIDING METHOD

— Small entity status under 37 CFR 1.9(f) is  
claimed and the amounts shown in parentheses below have been  
employed.

The following are enclosed:

X Specification

X 22 Claims(s) (including 3 independent claim(s))

X Unsigned Oath or Declaration, Power of Attorney &  
Petition

X 15 Sheet(s) of Drawings

X Our check for \$796.00 calculated as follows:

Basic Fee of \$760 (\$380) ..... \$ 760.00

2 Total Claims in excess of 20 at \$18 (\$9) .....\$36.00

— Ind. Claims in excess of 3 at \$78 (\$39) .....\$0.00

— Fee of \$260 (\$130) for Mult. Dep. Claim .....\$0.00

Total Filing Fee ..... **\$796.00**

Assignment Recording Fee of \$40 ..... \$0.00

— Certified copy of each of the following to  
substantiate the claim for priority:

<u>Application No.</u>	<u>Filing Date</u>	<u>Country</u>
P10-017017	January 29, 1998	Japan


X Please charge any additional fees required for the filing of this  
application and any other fees required during the pendency of  
this application or credit any overpayment to Deposit Account No.  
03-3125. A duplicate copy of this letter is enclosed.

Respectfully submitted,

COOPER & DUNHAM LLP

By:

Jay H. Maioli  
Jay H. Maioli  
Reg. No. 27,213



IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

Application for Letters Patent

Title : INFORMATION DISPLAYING SYSTEM,  
INFORMATION PROVIDING APPARATUS, AND  
INFORMATION PROVIDING METHOD

Inventor(s): Chiharu HIRONO

09230830330220

INFORMATION DISPLAYING SYSTEM, INFORMATION PROVIDING  
APPARATUS, AND INFORMATION PROVIDING METHOD

BACKGROUND OF THE INVENTION

Field of the Invention

5           The present invention relates to an  
information displaying system, an information providing  
apparatus, and an information providing method for  
displaying a map of a neighboring area of a designated  
point and a message corresponding thereto through a  
10       network.

Description of the Related Art

15           Nowadays, web pages have been widely used.  
The web pages are HTML (Hyper-Text Markup Language)  
files stored in WWW (World Wide Web) servers and  
published through Internet. Each web site has at least  
one web page. The representative page of each web site  
is referred to as home page. In the following  
description, a web page is referred to as home page. A  
network location of a home page is referred to as web  
20       site or simply site.

25           Since a home page is described in HTML that  
is a relatively simple language and published  
worldwide, it has been widely used as a personal  
information transmitting means and a business  
advertizing means.

          To browse an HTML file such as a home page, a  
WWW browser that is a computer application is used.

The WWW browser reads a designated file corresponding to for example an input URL (Uniform Resource Locator). When an address on Internet is contained in the file as an URL, a file corresponding to the address is searched and read through Internet. Likewise, as a URL, a local storage medium such as a hard disk of a personal computer on which the WWW browser is running can be designated.

When an HTML file is read by the WWW browser, the WWW browser performs various controls corresponding to the contents thereof. For example, corresponding to the contents of the HTML file, controlling portions such as buttons can be disposed on the WWW browser. Thus, the user can interactively operate the WWW browser with the controlling portions disposed thereon. For example, processes can be allocated to coordinates of image files on the WWW browser. Consequently, when the user designates a particular position with an image on the WWW browser, a process corresponding to the position is performed on the WWW browser.

An HTML file can contain a tag for reading another file. A process for reading another file from a particular HTML file is referred to as link. A link destination may be another URL. Thus, one HTML file can be linked to any file on Internet.

When a file read by the WWW browser is an HTML file, information corresponding to the file is

displayed on the WWW browser. When an image file is linked to an HTML file that is read, the URL of the image file is accessed. Thus, the image file is read and displayed on the WWW browser. Likewise, when audio data is linked, the URL thereof is automatically accessed. Thus, data of the audio file is reproduced. Of course, another type HTML file can be linked.

As described above, an HTML file can be automatically linked. Alternatively, an HTML file can be interactively linked by the user. When an HTML file contains a tag for manually linking the HTML file, a link button for controlling the linking of the HTML file is displayed on the WWW browser. When the user operates the link button in a predetermined manner, the HTML file is linked to a predetermined file.

There is a multimedia information searching home page for search information through a network. WWW sites have provided a huge amount of information of various types including technical information, financial information, shopping information, and restaurant information. The WWW sites are operated by various people and organizations (public organizations such as the central government, local governments, large companies, small companies and stores, and people). It is expected that such services using home pages will drastically grow.

The user can easily obtain shopping

information, event information, and so forth from such  
WWW sites. However, even if the user has obtained such  
information, he or she needs a map to visit the store  
or event place. Thus, when shopping information and  
5 event information are published on home pages,  
locations of stores and event places should be placed  
on maps. As described above, since home pages are  
created with HTML files, when image information of maps  
showing neighboring areas of the locations of the  
10 stores and event places is provided, the maps can be  
placed at particular positions of particular pages.

However, since roads and geographical shapes  
are very complicated, it is very difficult for a  
creator of a home page to create a map showing a  
15 neighboring area of a store or an event place and to  
place it to a particular page. When a creator of a  
home page draws a map, it is not accurate.

To solve such a problem, it is possible to  
provide a map information home page for displaying map  
20 information corresponding to input location information  
of latitude and longitude. When such a home page is  
available, after the user has obtained shopping  
information, event information, or the like, he or she  
opens a search page of such a map information home page  
25 and inputs location information of the obtained  
shopping information, event information, or the like.  
Thus, the user can know the location of the store,

event place, or the like on a map. When store names and event place names are correlated with location information, their maps can be displayed without necessity of location information of latitude and longitude.

Many advertisements have been placed on home pages. In this case, images files of advertisements are displayed on pages. On a home page about business related information, an advertisement relating thereto is placed. In other words, the target of the advertisement is a user who is interested therein. In other words, an advertisement placed on a home page depends on the contents thereof.

However, since the contents of home pages are normally fixed, in such a method, the genre of advertisements placed on a particular home page does not vary. Thus, an advertisement with a wider genre cannot be placed on a home page.

In addition, users are not interested in advertisements of specialized fields placed on home pages. Thus, the effects of advertisements are low. For example, when an advertisement of Okinawa (a region in Japan) is placed on a home page about Okinawa, it is expected that users who see the home page are not interested in the advertisement. On the other hand, an article may be placed on a home page that does not relate to Okinawa. When an advertisement about Okinawa

is placed on such a home page, it is expected that the effect of the advertisement becomes high. However, it is troublesome to select an advertisement from the related genre whenever an article of a home page is updated.

#### OBJECTS AND SUMMARY OF THE INVENTION

Therefore, an object of the present invention is to provide an information displaying system that flexibly displays an advertisement and a message corresponding thereto so as to allow a user to be interested therein.

A first aspect of the present invention is an information displaying system for displaying information corresponding to a geographical location, comprising a display commanding means pre-assigned a unique ID, an information displaying means for displaying information corresponding to a command received from the display commanding means, a first data storing means for storing map drawing element data for drawing a map, a second data storing means for storing a geographical location corresponding to contents displayed corresponding to the command received from the display commanding means and first attribute information in such a manner that the geographical location and the first attribute information are correlated with the ID, a map drawing commanding means, linked from the display commanding



means, for searching the first data storing means so as to draw the map corresponding to the location searched from the second data storing means corresponding to the ID, wherein the map corresponding to a command received from the map drawing commanding means is displayed by the information displaying means.

A second aspect of the present invention is an information providing apparatus for providing information corresponding to a geographical location, comprising a first data storing means for storing map drawing element data for drawing a map, a second data storing means for storing a geographical location corresponding to a particular ID and first attribute information in such a manner that the geographical location and the first attribute information are correlated with the ID, a map drawing commanding means for searching the first data storing means so as to draw the map corresponding to the location searched from the second data storing means corresponding to the ID, wherein when display commanding means assigned the ID is linked to the map drawing commanding means, the map drawing commanding means causes information displaying means to draw and display the map.

A third aspect of the present invention is an information providing method for providing information corresponding to a geographical location, comprising the steps of (a) storing map drawing element data for

drawing a map to first data storing means, (b) storing  
a geographical location corresponding to a particular  
ID and first attribute information to second data  
storing means in such a manner that the geographical  
location and the first attribute information are  
correlated with the ID, (c) searching the first data  
storing means so as to draw the map corresponding to  
the location searched from the second data storing  
means corresponding to the ID, wherein when display  
commanding means assigned the ID is linked, the step  
(c) is performed for information displaying means to  
draw and display the map.

These and other objects, features and  
advantages of the present invention will become more  
apparent in light of the following detailed description  
of a best mode embodiment thereof, as illustrated in  
the accompanying drawings.

#### BRIEF DESCRIPTION OF THE DRAWINGS

Fig. 1 is a schematic diagram showing an  
example of the structure of an information displaying  
system according to an embodiment of the present  
invention;

Fig. 2 is a schematic diagram showing an  
example of the data structure of an advertisement  
correlation database;

Fig. 3 is a flow chart showing a displaying  
process of a map home page of the information

displaying system;

Fig. 4 is a schematic diagram showing an example of a home page for guiding a company or a store;

5 Fig. 5 is a schematic diagram showing an example of a map home page;

Fig. 6 is a schematic diagram showing an example of a registration page for adding and changing information for a location search database;

10 Fig. 7 is a schematic diagram showing an example of a business category input page;

Fig. 8 is a schematic diagram showing an example of a map registration page for inputting map information;

15 Fig. 9 is a schematic diagram showing an example of a map registration page for inputting map information;

20 Fig. 10 is a schematic diagram showing an example of a point registration screen for registering a point of a company or a store;

Fig. 11 is a schematic diagram showing an example of a guide screen for guiding a linking method for a registered map;

25 Fig. 12 is a schematic diagram showing an example of a map home page for displaying convenient information on a map of a company or a store;

Fig. 13 is a schematic diagram showing an

example of the structure of a system of which a publication database is added to a map home page server according to another embodiment of the present invention;

5           Fig. 14 is a schematic diagram showing an example of a map home page in the case that a publication database is added;

10           Fig. 15 is a schematic diagram showing an example of a home page for a searching service to a location search database;

          Fig. 16 is a schematic diagram showing an example of searched results of the searching service to the location search database; and

15           Figs. 17A and 17B are flow charts showing a process for restricting the display of a map.

#### DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

20           Next, an embodiment of the present invention will be described. The information displaying system according to the present invention has a map home page linked to a registered home page. The map home page displays a map. Information such as an advertisement is displayed on the map home page. The information displayed on the map home page depends on the business category of the home page, the location of the store or  
25           company of the home page, and the date and time at which the information is searched.

          Fig. 1 is a schematic diagram showing an

example of the structure of the system according to an embodiment of the present invention. A home page server 1 and a map home page server 2 are connected through Internet 3. The home page server 1 is a WWW server. A user terminal 4 is connected to Internet 3 through a public telephone line or the like. Such servers and terminals are identified with unique IP (Internet Protocol) addresses. In addition, they can mutually communicate with each other using IP addresses. Any server and any terminal connected to Internet 3 are treated as the home page server 1 and the user terminal 4, respectively.

The user terminal 4 is for example a personal computer. The user terminal 4 comprises structural portions (such as a CPU, a RAM, and a ROM), a displaying unit (that displays color/monochrome graphic data), and an inputting device (that allows the user to input data as coordinate data on the displaying unit). The user terminal 4 has a WWW browser. The user terminal 4 accesses the home page server 1 through Internet 3. A transmitted HTML file is read by the WWW browser and displayed on the displaying unit. The user terminal 4 may be an information unit other than the personal computer.

The home page server 1 is composed of a plurality of computers that are mutually connected to each other. The home page server 1 stores an HTML file

for a home page and image data displayed on pages. In other words, a home page is registered to the home page server 1 and thereby a WWW site is formed. The home page registered to the home page server 1 is assigned a unique ID number by the administrator of the map home page server 2, With the unique ID number, the information displaying system according to the present invention can be used.

When the information displaying system is used, a home page registered to the home page server 1 is linked to a home page registered to the map home page server 2. In addition, the ID number as an argument is passed to the map home page server 2. Thereafter, a process of the map home page server 2 is executed.

The map home page server 2 is composed of one computer or a plurality of computers that are connected to each other. The map home page server 2 has a plurality of databases 10, 11, 12, and 13. The database 10 is a map database that stores map information. The database 11 is a location search database that stores location search information. The database 13 is an advertisement correlation database that stores advertisement correlation information.

The map home page server 2 searches the map database 10 and the location search database 11 corresponding to an ID number as an argument received

from a home page as a link source and creates map image data. The map home page server 2 searches the advertisement database and advertisement correlation database 13 with predetermined search parameters and obtains advertisement image data. The map home page server 2 creates a map home page with the obtained map image data and advertisement image data. The created map home page is displayed on the user terminal 4.

Next, those databases will be described in detail. The map database 10 stores map drawing element data necessary for drawing a map corresponding to latitude and longitude. The map drawing element data is composed of line data, paint data, and character data. The line data is used to draw for example roads and railroad tracks. The paint data is used to draw for example a sea. The character data is used to display for example geographical names. The user inputs search parameters to the map database 10. The search parameters are the latitude and longitude at the center position of an area of a desired map, the size thereof, and the scale thereof. The user designates the size in pixels of the displaying unit of the user terminal 4.

Map data is searched from the map database 10 corresponding to the search parameters. Thus, map drawing element data is obtained. With the obtained map drawing element data, map image data is created.

When the user designates coordinates of a desired location on the map, the desired location is highlighted with a marker. The created map image data is displayed on the map home page.

5           The location search database 11 stores map drawing parameters correlated with an ID number of a home page of the home page server 1. The map drawing parameters are for example the scale of a map, latitude and longitude at the center position of the map, the  
10           size of the map, and marker information. In addition, the location search database 11 stores store information parameters correlated to the ID number of the home page. The information parameters are for example the name, address, telephone number, business  
15           hour, and business category of a company or a store. When the location search database 11 is searched corresponding to an ID number. Parameters correlated with the ID number are obtained as attribute information of the home page.

20           Information stored in the location search database 11 is registered on a particular home page by a designated person of a company or a store that uses the information displaying system. It is preferable to select a relevant business category from a pre-  
25           designated list.

          The advertisement database 12 stores advertisement image data displayed on the map home



page. In addition, the advertisement database 12 stores advertisement attribute information. The advertisement attribute information is composed of for example the business category of an advertisement and the genre of commodities thereof. As attribute conditions, it is preferable to add time conditions such as a time zone, days of week, and the period of the advertisement placed on the home page. Advertisement image data searched and obtained from the advertisement database 12 is placed at a peripheral portion of a map on the map home page.

The advertisement correlation database 13 correlates advertisement image data with other parameters in three correlating types. In the first correlation type, the advertisement correlation database 13 correlates a map linked from a home page with the business category of an advertisement. For example, when a home page of a company whose business category is a personal computer is linked to the map home page, it is expected that effective business categories of advertisements are publishers that publish magazines about personal computers and software companies.

In the second correlation type, the advertisement correlation database 13 correlates latitude and longitude information with business categories of advertisements. In the second

correlation type, when a map of a resort area is displayed, advertisements of hotels, travel agents, railway companies, and travel guide publishers in the resort area are displayed.

5           The third correlation type relates to time. In other words, the advertisement correlation database 13 correlates date and time at which the home page of the home page server 1 is linked to the map home page and a map is searched from the map home page server 2  
10       with an advertisement.

          In the third correlation type, date and time are correlated with advertisements. Thus, for example, an advertisement of bargain information of a department store or event information can be displayed in a  
15       predetermined time period. Alternatively, when time is correlated with advertisements, an advertisement of a soft drink is displayed in the daytime, while an advertisement of an alcoholic drink is displayed in the nighttime. In such a manner, advertisements can be  
20       switched corresponding to time zones. In addition, an advertisement of a business company is displayed on weekdays, while an advertisement of an amusement company is displayed on weekend.

          Fig. 2 is a table showing an example of the  
25       data structure of the advertisement correlation database 13. The first line of the table represents field names. Next, each field of the table will be

described. Field "advertisement name" represents a character string of an advertisement. The advertisement name is not displayed on the map home page. In this example, the field "advertisement name" on the second line of the table represents an advertisement of "Weekly Tokyo Guide, Issue on November 22, 1997". The field "advertisement name" on the third line of the table represents an advertisement of "XYZ Insurance Company".

Field "image file name" represents an image file name of an advertisement displayed on the map home page. Alternatively, field "image file name" may represent a URL of an image file. As the searched results of the map home page server 2, image file names are obtained.

Field "location dependency flag" represents a location dependency flag. The location dependency flag represents whether or not the advertisement in field "advertisement name" relates to the location of a map displayed on the map home page. When the value of the location dependency flag is "1", the advertisement relates to the location of the map. When the location dependency flag is "0", the advertisement does not relate to the location of the map. In this example, the advertisement of the magazine on the second line is displayed when a map of a predetermined area (for example, Tokyo) is displayed on the map home page. In

contrast, the advertisement of the insurance company on the third line is displayed regardless of the area of the map.

An area is designated corresponding to data in fields "minimum longitude", "minimum latitude", "maximum longitude", and "minimum latitude" as will be described later. The advertisement database 12 may store display area information as advertisement attribute information.

In the fields "minimum longitude", "minimum latitude", "maximum longitude", and "maximum latitude", values that represent the range of the center position of a map in which an advertisement is placed are written. When the center position of a map displayed on the map home page is inside the range defined with the four fields, the advertisement is displayed. Fields "start date/time" and "end date/time" represent a period for which an advertisement is placed.

Field "business category" represents a business category of an advertisement that is displayed on the map home page. In field "business category", a plurality of business categories can be designated.

The advertisement correlation database 13 is created by for example an administrator of the map home page server 2. The contents of the individual fields of the advertisement correlation database 13 depend on contracts made between companies and so forth that want

to place advertisements on the map home page and the provider side of the map home page server 2, predictable advertisement effects, and so forth.

In the above-described example, the advertisement correlation database 13 is structured as a table. However, it should be noted that the advertisement correlation database 13 is not limited to such a table. Instead, the advertisement correlation database 13 may be composed of a plurality of tables with a common key of a particular field. The tables may be shared by the advertisement database 12 and the advertisement correlation database 13.

Next, a process for displaying a map home page in the information displaying system will be described. Fig. 3 is a flow chart showing the process. First of all, the user terminal 4 accesses a home page that guides a company or a store and that has been registered to the home page server 1. The user terminal 4 requests the home page server 1 for a map of the company or the store. The home page is assigned a unique ID number by an administrator of the map home page server 2 beforehand. The request is issued to the map home page server 2. In addition to the request, the ID number is transmitted to the map home page server 2. When the ID number has been transmitted to the map home page server 2, the map home page for a map and an advertisement is displayed on the user terminal

4 (at step S10). The map home page contains various commands that cause the map home page server 2 to display a map and so forth.

5 The map home page server 2 searches the location search database 11 corresponding to the received ID number (at step S11). The map home page server 2 searches the map database 10 with map drawing parameters obtained as the searched results of the location search database 11. Thus, the map home page server 2 obtains map drawing element data and creates map image data. The created map image data is transmitted to the user terminal 4 (at step S12). The map image of the map home page is displayed on the user terminal 4.

10 At step S13, the map home page server 2 searches a relevant business category from the advertisement correlation database 13 corresponding to the obtained business category information. At step S14, the map home page server 2 searches an advertisement of the searched business category from the advertisement database 12. The obtained advertisement image data as the searched results is transmitted to the user terminal 4. The advertisement image data of the map home page is displayed on the user terminal 4 (at step S15).

20 Next, the process for displaying the map home page will be described in detail. First of all, the

user operates the user terminal 4 so as to access the home page server 1 for a home page of "ABC Store". The home page is assigned an ID number for the map home page of the map home page server 2 beforehand.

5           An HTML file having a command for displaying a relevant home page is transmitted from the home page server 1 to the user terminal 4 through Internet 3. For example, the WWW browser installed in the user terminal 4 reads the HTML file. As shown in Fig. 4, 10 the home page of the "ABC Store" 40 is displayed. In this example, as a guide of the "ABC Store", sales information, the address of the store, and the telephone number of the store are displayed on the home page 40. In addition, a link button 41 for displaying 15 the map of the "ABC Store" on the map home page is placed on the home page 40.

          The link button 41 causes a particular request to be issued to the WWW server corresponding to a special expression referred to as HTML anchor. When 20 the link button 41 is pressed, a particular argument (an assigned ID number) is passed to a link destination (namely, the home page 40). For example, the link button 41 in the HTML file is expressed as follows.

25           <A href = "http://www.mapcenter.co.jp/cgi-bin /showMap? ID=12345"><IMG src="map.gif"></A>

          In this example, the URL of the map home page

server 2 is "http://www.mapcenter.co.jp". In addition,  
an application "showMap" using CGI (Common Gateway  
Interface) starts. Moreover, an ID number "12345" as  
an argument is passed to the application "showMap". In  
5 other words, the ID number "12345" is assigned to the  
home page 40 beforehand. "map.gif" is a image file  
name for displaying the link button 41.

When the user clicks the link button 41 on  
the user terminal 4, the map home page server 2 is  
10 searched corresponding to the URL contained in the HTML  
file through Internet. After the map home page server  
2 has been searched, the application "showMap" is  
started on the map home page server 2. The home page 40  
(home page server 1) passes the ID number as an  
15 argument to the application "showMap".

The application "showMap" creates an HTML  
file contains a command for displaying a map home page  
corresponding to a passed ID number. The created HTML  
file is transmitted to the user terminal 4.

20 When the application "showMap" creates an  
HTML file, the application "showMap" searches the  
location search database 11 corresponding to the ID  
number and obtains shop information parameters. The  
shop information parameters are contained in the HTML  
25 file so that a predetermined layout is displayed on the  
map home page.

The HTML file contains layout data such as



map image data, various types of character data, and advertisement image data. In addition, the HTML file contains map image data creating conditions and advertisement searching conditions. When the WWW browser of the user terminal 4 reads the HTML file, the WWW browser requests the map home page server 2 for image data corresponding to the contents of the HTML file. The WWW browser directly displays the character data.

Fig. 5 is a schematic diagram showing an example of a map home page displayed on the user terminal 4. In Fig. 5, store information 43 of "ABC Store" is displayed as a character string corresponding to store information parameters contained in an HTML file on the map home page 42. At this point, a map image 44 and advertisement images 45 are not displayed. A controller 46 has a group of buttons as enlargement/reduction buttons and map center position moving buttons.

The map home page server 2 executes a program for drawing a map corresponding to a request from the user terminal 4. The program searches the location search database 11 corresponding to the passed ID number as an argument and obtains map display parameters as the searched results. The program searches the map database 10 corresponding to the map scale, the latitude and longitude at the center

position of the map as the obtained map display parameters. The program draws a map with map drawing element data obtained as the searched results, highlights the position of the store (or company) guided by the home page 40 with a predetermined marker, and thereby creates map image data. The created map image data is transmitted to the user terminal 4. The user terminal 4 displays the map image data as the map image 44. In Fig. 5, the marker that highlights the store is represented with a black dot.

On the other hand, the map home page server 2 executes a program for searching the advertisement correlation database 13 corresponding to an advertisement image data request received from the user terminal 4. As described above, since the application "showMap" has searched the store information parameters from the location search database 11, the program searches the advertisement correlation database 13 corresponding to the business category as the store information parameters.

As described above, in the advertisement correlation database 13, advertisement images are correlated with at least one business category by an administrator or the like of the map home page server 2. In the example shown in Fig. 4, it is assumed that the business category of "ABC Store" has been categorized as "Apparel Retailers". As expected

business categories of effective advertisements to general users who are interested in apparels are for example are apparel makers and publishers of apparel magazines. Although the business categories of  
5 esthetic salons and cosmetics makers do not directly relate to apparels, advertisements of these business categories will be effective.

In the advertisement correlation database 13, at least one business category that is expected to be effective has been registered to field "business  
10 category". Thus, when the advertisement correlation database 13 is searched with a particular key (in this example, "Apparel Retailers"), at least one business category that is supposed to be correlated with  
15 "Apparel Retailers" is searched.

The searching program also searches the advertisement database corresponding to the searched business category and obtains advertisement image data corresponding to the searched business category. The  
20 searched advertisement image data is transmitted to the user terminal 4. The searched advertisement image data is displayed as advertisement images 45 of the map home page 42 on the user terminal 4.

The search conditions of the searching  
25 program are not limited to business categories. Instead, as described above, in the advertisement correlation database 13, advertisements are correlated

with latitude and longitude and with time conditions. As search conditions, such items can be added. Thus, for example, when the business category of the home page 40 is a publisher for an apparel magazine, an advertisement of a magazine can be displayed before three days of the release of the magazine until one week after the release of the magazine. In addition, only an advertisement of an esthetics salon located within 1 km of the "ABC Store" can be searched corresponding to the latitude and longitude information.

Next, a method for adding and changing information of the location search database 11 will be described. Information stored in the location search database 11 is added and changed on a particular home page (this home page is referred to as registration home page) of the map home page server 2. Information is registered on the user terminal 4. The user terminal 4 accesses the registration home page and the WWW browser of the user terminal 4 displays the registration home page.

Fig. 6 is a schematic diagram showing an example of a registration page 50 of the registration home page. The registration page 50 has input fields for information other than a map. Text data is input to the input fields. On the other hand, a business field is selected from a group of pre-designated

alternatives. An inputting portion 51 has large business category names and selection buttons corresponding thereto. The user selects a proper business category with the relevant selection button in the inputting portion 51. After the user has input information into the input fields and has selected the business category, he or she clicks an input button 52. Thus, the registering operation on the registration page 50 is completed. The registered information is stored in the location search database 11.

When information stored in the location search database 11 is changed, the information may be displayed in the input fields and the inputting portion 51 on the registration page 50. When the registering user inputs only desired information and clicks the input button 52, the input information is stored in the location search database 11.

After the input button 52 has been pressed and desired information has been registered on the registration page 50, a business category input page 53 shown in Fig. 7 is displayed. On the business category input page 53, small business categories are displayed. Referring to Fig. 7, an inputting portion 54 has small business category names and selection buttons corresponding thereto. The small business category input page 53 is adaptively structured corresponding to the large business category selected on the

registration page 50.

Fig. 7 shows an example in the case that the large business category "restaurants" has been selected in the inputting portion 51. The inputting portion 54 has small business category names and selection buttons corresponding thereto. When the user clicks an input button 55, the small business category that has been selected in the inputting portion 54 is stored in the location search database 11.

After the input button 55 has been pressed and the business category has been input, a map information input page is displayed. Figs. 8 and 9 show examples of the map registration page for inputting map information. The map registration page 60 has a map displaying portion 61, a map controlling portion 62, and a map setup end button 63. The map displaying portion 61 displays a map. The map controlling portion 62 controls enlargement/reduction of a map displayed on the map displaying portion 61 and movement of the display range of the map.

The map displaying portion 61 of the map registration page 60 shows a map in a large scale as shown in Fig. 8. The registering user operates controllers of a map controlling portion 62 so that a desired location is accurately displayed on an enlarged map in the map displaying portion 61. As shown in Fig. 9, when an enlarged map is displayed in the map

displaying portion 61, the registering user clicks a map setup end button 63.

After the map setup end button 63 has been pressed, as shown in Fig. 10, a point registration screen 64 for registering a point is displayed. The point registration screen 64 is different from the map registration page 60. Alternatively, the point registration screen 64 may be in common with the map registration page 60 except for messages displayed thereon. The registering user clicks a desired location with a mouse or the like. The user terminal 4 converts the designated coordinates into latitude and longitude information. The latitude and longitude information is stored to the location search database 11.

After information has been registered to the point registration screen 64, a guide screen for guiding a linking method to the registered map is displayed as shown in Fig. 11. On the linking method guide screen 65, an anchor 66 for linking the home page to the registered map is displayed. The anchor 66 is contained in the HTML file for the home page of the store or company. In this example, the anchor 66 is directly copied from the linking method guide screen 65 and pasted to the HTML file. When the HTML file contains the anchor 66, the home page of the HTML file can be linked to the map home page 42 shown in Fig. 5.

In the above-described example, only the location of the store or company guided on the home page as the link source is displayed on the map image 44 of the map home page 42. However, the present invention is not limited to such an example. In other words, information that is expected to be convenient for the user who uses the map home page 42 can be displayed on the map image 44.

Fig. 12 shows an example of the map home page 42 on which a map image 44' of information of facilities (police sub-station, pedestrian bridges, neighboring buildings, major roads, and so forth) and a guest parking is displayed. Such information can be registered on the point registration screen 64 shown in Fig. 10. The registered information is stored in for example the location search database 11.

As another example of the embodiment, another database may be added to the map home page server 2. Fig. 13 is a schematic diagram showing an example of which a publication database 14 is added to the map home page server 2. The publication database 14 is correlated with for example publication names. The publication database 14 stores outlines of publications, business categories corresponding to the publications, latitude and longitude information, and so forth. In addition, the publication database 14 may store time conditions of the publications (such as



released dates of the publications and sales periods of the publications).

Fig. 14 is an example of the map home page 42 in the case that the publication database 14 is added.

5 In Fig. 14, information stored in the publication database 14 is displayed on the map home page 42 shown in Fig. 12. Publication information 47 is displayed on the map home page 42. In this example, as the publication information 47, a magazine name and an  
10 outline thereof are displayed. In addition, the publication information 47 may contain an HTML anchor. Thus, the publication information 47 may be used as a link button to the home page of the publisher of the publication information 47.

15 The location search database 11 stores much information of stores and companies. Thus, a service that searches the location search database 11 and provides the user with searched information is expected. Fig. 15 shows an example of a home page for  
20 such a searching service. The home page for the searching service is present on the map home page server 2. The home page for the searching service is displayed on the user terminal 4.

25 In this example, the home page for the searching service has a search page 70. The search page 70 has an area selecting portion 71, a business category selecting portion 72, and a name inputting

portion 74. The area selecting portion 71 lists  
searchable area names. The user of the searching  
service designates a desired area in the area selecting  
portion 71. In this case, a plurality of areas are  
5 preferably designated. The business category selecting  
portion 72 has large business category names and  
selecting buttons corresponding thereto. When the  
searching user clicks a desired selection button, he or  
she can search the desired business category. The user  
10 may select a plurality of business categories at a  
time. When the user clicks a search button 73, the  
location search database 11 is searched corresponding  
to conditions selected in the selecting portions 71 and  
72.

15 Fig. 16 shows an example of searched results.  
Referring to Fig. 16, a search result page 75 lists  
searched results. When the user clicks a map button 76  
corresponding to the searched results, the home page  
for the searching service is linked to a relevant map  
20 home page 42.

When the user wants to search a particular  
company or store without information of an area or a  
business category thereof, he or she directly inputs  
the name of the company/store to the name inputting  
25 portion 74 and clicks the search button 73'. Thus, the  
location search database 11 is searched with the  
company/store name and the search result page 75 is

displayed.

On the other hand, the map displaying service WWW server is linked from many home pages. Thus, many users access the map home page server 2. Consequently, since the load applied to the map home page server 2 becomes high, it takes a long time for a response against an access from the user terminal 4 to the map home page server 2. Thus, the users of the searching service may be frustrated.

To solve such a problem, it is expected to restrict operations of the user against the map home page. For example, the user is restricted to maps of areas close to a designated area. In addition, the number of times of an enlarging/reducing operation and a moving operation of a map may be restricted. When the number of users who are accessing the map displaying service WWW server is small, such restrictions may not be applied.

Figs. 17A and 17B are flow charts showing such a process. Fig. 17A shows a linking operation with the link button 41 on the home page 40 for guiding a company or a store. When the link button 41 is clicked on the home page 40, a link request is issued from the home page 40 to the map home page server 2. At this point, a variable COUNT is set to "1". Latitude and longitude information at the center position of the map is searched from the location

search database 11. With the latitude and longitude information, a variable KEIDO\_BEGIN is set to the longitude value at the center position of the map. Likewise, a variable IDO\_BEGIN is set to the latitude value at the center position of the map. After required variables have been set at step S20, the flow advances to step S21. At step S21, the map home page server 2 transmits the map home page 42 to the user terminal 4.

Fig. 17B shows a restricting process against the enlarging/reducing operation and the center position moving operation for the map image 44 by the controller 46 on the user terminal 4. This restricting process is performed by the map home page server 2. When the user terminal 4 accesses the map home page server 2, the map home page server 2 determines whether or not the number of users who are accessing the map home page server 2 does not reach a predetermined upper limit value (at step S30). When the determined result is Yes, the flow advances to step S37. At step S37, the map home page server 2 transmits the map home page 42 to the user terminal 4.

When the determined result at step S30 is No, the flow advances to step S31. At step S31, it is determined whether or not the value of the variable COUNT does not reach a predetermined upper limit value. As will be described later, the variable COUNT

represents the number of times of the operation of the controller 46 on the user terminal 4. When the upper limit value is assigned to the variable COUNT, the number of times of the operation of the controller 46 can be restricted.

When the determined result at step S31 is No, the flow advances to step S38. At step S38, the controller 46 transmits a message to the user terminal 4 so that the user knows that a map cannot be displayed on the map home page 42.

On the other hand, when the determined result at step S31 is Yes, the flow advances to step S32. At step S32, the variable COUNT is incremented by "1". In addition, the operation of the controller 46 on the user terminal 4 is accepted. In other words, corresponding to the operation of the controller 46, the current map image is enlarged/reduced or the center position of the current map image is moved. The resultant map image data is transmitted to the user terminal 4 and displayed on the map home page 42. The center latitude and center longitude of the new map image data are placed in the variable IDO and the variable KEIDO, respectively.

At steps S33 to S36, it is determined whether or not the center latitude and center longitude of the new map do not reach predetermined ranges of those of the original map. The moving range of the center

position of the new map against the original map is pre-designated in latitude and longitude. At steps S33 to S36, the difference between the variable KEIDO\_BEGIN and the variable KEIDO is compared with the longitude range. In addition, the difference between the variable IDO\_BEGIN and the variable IDO is compared with the latitude range. Corresponding to the compared results, it is determined whether or not the moving range of the center position of the new map does not reach the latitude range and the longitude range.

When at least one of the determined results at steps S33 to S36 is No, since the moving range reaches the latitude range and the longitude range, the flow advances to step S38. At step S38, a message is displayed on the user terminal 4 so that the user knows that a map cannot be displayed.

On the other hand, when all the determined results at step S33 to S36 are Yes, the flow advances to step S37. At step S37, the new map image data is transmitted to the user terminal 4.

In the above-described example, the home page 40 for guiding a company or a store is present in the home page server 1. However, the present invention is not limited to such an example. In other words, the home page 40 may be present in the map home page server 2.

In the above-described example, the databases

10, 11, 12, 13 and 14 are directly connected to the map home page server 2. However, the present invention is not limited to such an example. In other words, the databases 10, 11, 12, 13, and 14 may be distributively disposed on Internet 3.

In addition, anchors may be placed on the advertisement images 45 on the map home page 42 so as to link them to other home pages. For example, the advertisement images 45 may be linked to respective home pages of companies and stores that are advertisers. Alternatively, the map home page 42 may be displayed corresponding to the advertisement images 45.

As described above, according to the present invention, when a home page for guiding a company, a store, or the like to the map home page, a map of a neighboring area thereof is displayed on the map home page. In addition, an advertisement corresponding to a business category of the company or store is displayed at a peripheral portion of the map. Thus, it is expected that the user who uses the home page of the company or store is interested in the advertisement. Consequently, a high advertisement effect can be obtained.

In addition, since an advertisement is displayed depending on latitude and longitude of the map and time conditions thereof, a higher advertisement

effect can be expected.

In addition, according to the present invention, an advertisement can be properly selected depending on latitude and longitude information. Thus, an advertisement can be displayed for users who need map information of local areas as well as map information of large amusement areas.

In addition, it is assumed that the number of advertisements required by small companies, stores, and people is small. Thus, when an advertisement is charged for each placement with the system according to the present invention, a small company, a small store, and a person can place an advertisement at low cost.

According to another embodiment of the present invention, an advertisement for a publication in an area of a map that the user wants to see is automatically searched and displayed at a peripheral portion of the map on the map home page. For example, when a map of an amusement area is displayed on the map home page, the title of a magazine that features the area is displayed. When a resort area is displayed on the map home page, the title of a magazine that features the amusement area and the title of a newly released book that deals with the area are displayed at a peripheral portion of the map. Thus, the user can easily find publications that deal with a desired area. Consequently, since the user has a motivation for



purchasing such publications, a high advertisement effect can be obtained.

In addition, according to the present invention, the creator of a home page can place a map on his/her home page by inputting a mark and a character string on a map image provided by the map home page server without need to create a detailed accurate map.

Although the present invention has been shown and described with respect to a best mode embodiment thereof, it should be understood by those skilled in the art that the foregoing and various other changes, omissions, and additions in the form and detail thereof may be made therein without departing from the spirit and scope of the present invention.

What is claimed is:

1. An information displaying system for displaying information corresponding to a geographical location, comprising:

5 display commanding means pre-assigned a unique ID;

information displaying means for displaying information corresponding to a command received from said display commanding means;

10 first data storing means for storing map drawing element data for drawing a map;

second data storing means for storing a geographical location corresponding to contents displayed corresponding to the command received from said display commanding means and first attribute information in such a manner that the geographical location and the first attribute information are correlated with the ID;

20 map drawing commanding means, linked from said display commanding means, for searching said first data storing means so as to draw the map corresponding to the location searched from said second data storing means corresponding to the ID,

25 wherein the map corresponding to a command received from said map drawing commanding means is displayed by said information displaying means.

2. The information displaying system as set

forth in claim 1, further comprising:

third data storing means for storing  
advertisement data displayed by said information  
displaying means and second attribute information that  
5 represents an attribute of the advertisement; and

advertisement display commanding means,  
linked from said display commanding means, for causing  
said information displaying means to display the  
advertisement with the advertisement data searched from  
10 said third data storing means with a correlation of the  
first attribute information searched from said second  
data storing means corresponding to the ID and the  
second attribute information,

wherein the advertisement corresponding to  
15 the command received from said advertisement display  
commanding means and the map corresponding to the  
command received from said map drawing commanding means  
are displayed by said information displaying means.

3. The information displaying system as set  
20 forth in claim 1,

wherein the first attribute information is a  
business category corresponding to the ID.

4. The information displaying system as set  
forth in claim 2,

25 wherein the second attribute information is a  
business category of the advertisement.

5. The information displaying system as set

forth in claim 2,

wherein the second attribute information is location information of the advertisement.

6. The information displaying system as set forth in claim 2,

wherein the second attribute information is time information of the advertisement.

7. The information displaying system as set forth in claim 2,

wherein the second attribute information stored in said third data storing means is composed of the contents of the advertisement, the geographical location information of the advertisement, the business category of the advertisement, and the effective period of the advertisement.

8. The information displaying system as set forth in claim 2,

wherein said display commanding means has linking means for linking said map drawing commanding means and said advertisement display commanding means.

9. An information providing apparatus for providing information corresponding to a geographical location, comprising:

first data storing means for storing map drawing element data for drawing a map;

second data storing means for storing a geographical location corresponding to a particular ID

and first attribute information in such a manner that the geographical location and the first attribute information are correlated with the ID;

map drawing commanding means for searching  
5 said first data storing means so as to draw the map corresponding to the location searched from said second data storing means corresponding to the ID,

wherein when display commanding means  
assigned the ID is linked to said map drawing  
10 commanding means, said map drawing commanding means causes information displaying means to draw and display the map.

10. The information providing apparatus as set forth in claim 9, further comprising:

15 third data storing means for storing advertisement data displayed by said information displaying means and second attribute information that represents an attribute of the advertisement; and

advertisement display commanding means for  
20 causing said information displaying means to display the advertisement with the advertisement data searched from said third data storing means with a correlation of the first attribute information searched from said second data storing means corresponding to the ID and  
25 the second attribute information,

wherein when said advertisement display commanding means and said map drawing command means are

linked from said display commanding means, said advertisement display commanding means causes said information displaying means to display the advertisement and said map drawing commanding means causes information displaying means to draw and display the map.

11. The information providing apparatus as set forth in claim 9,

wherein the first attribute information is a business category corresponding to the ID.

12. The information providing apparatus as set forth in claim 10,

wherein the second attribute information is a business category of the advertisement.

13. The information providing apparatus as set forth in claim 10,

wherein the second attribute information is location information of the advertisement.

14. The information providing apparatus as set forth in claim 10,

wherein the second attribute information is time information of the advertisement.

15. The information providing apparatus as set forth in claim 10,

wherein the second attribute information stored in said third data storing means is composed of the contents of the advertisement, the geographical

location information of the advertisement, the business category of the advertisement, and the effective period of the advertisement.

16. An information providing method for providing information corresponding to a geographical location, comprising the steps of:

(a) storing map drawing element data for drawing a map to first data storing means;

(b) storing a geographical location corresponding to a particular ID and first attribute information to second data storing means in such a manner that the geographical location and the first attribute information are correlated with the ID;

(c) searching the first data storing means so as to draw the map corresponding to the location searched from the second data storing means corresponding to the ID,

wherein when display commanding means assigned the ID is linked, the step (c) is performed for information displaying means to draw and display the map.

17. The information providing method as set forth in claim 16, further comprising the steps of:

(d) storing advertisement data displayed by the information displaying means and second attribute information that represents an attribute of the advertisement to third data storing means; and

(e) causing the information displaying means to display the advertisement with the advertisement data searched from said third data storing means with a correlation of the first attribute information searched from the second data storing means corresponding to the ID and the second attribute information,

wherein when the display commanding means is linked, the step (e) and the step (c) are performed for the information displaying means to display the advertisement and draw and display the map.

18. The information providing method as set forth in claim 16,

wherein the first attribute information is a business category corresponding to the ID.

19. The information providing method as set forth in claim 17,

wherein the second attribute information is a business category of the advertisement.

20. The information providing method as set forth in claim 17,

wherein the second attribute information is location information of the advertisement.

21. The information providing method as set forth in claim 17,

wherein the second attribute information is time information of the advertisement.

22. The information providing method as set forth



in claim 17,

wherein the second attribute information  
stored in said third data storing means is composed of  
the contents of the advertisement, the geographical  
location information of the advertisement, the business  
category of the advertisement, and the effective period  
of the advertisement.

5

## ABSTRACT OF THE DISCLOSURE

An information displaying system for displaying information corresponding to a geographical location is disclosed, that comprises a display commanding means pre-assigned a unique ID, an information displaying means for displaying information corresponding to a command received from the display commanding means, a first data storing means for storing map drawing element data for drawing a map, a second data storing means for storing a geographical location corresponding to contents displayed corresponding to the command received from the display commanding means and first attribute information in such a manner that the geographical location and the first attribute information are correlated with the ID, a map drawing commanding means, linked from the display commanding means, for searching the first data storing means so as to draw the map corresponding to the location searched from the second data storing means corresponding to the ID, wherein the map corresponding to a command received from the map drawing commanding means is displayed by the information displaying means.

Fig. 1








Fig. 4





Fig. 5



**Fig. 6**

50

STORE/COMPANY NAME

ZIP CODE

ADDRESS

TELEPHONE NUMBER

FAX NUMBER

BUSINESS HOURS TO

HOLIDAYS

LARGE BUSINESS CATEGORY

○ RESTAURANTS ○ AMUSEMENT/SPORTS FACILITIES

○ STORES ○ SERVICES

○ COMPANIES ○ PUBLIC FACILITIES/PUBLIC OFFICES

INPUT

51

52

*Fig. 7*






Fig. 8







Fig. 9



*Fig. 10*



*Fig. 11*



*Fig. 12*




Fig. 13




Fig. 14




Fig. 15

70

71

72

73

73'

74

SELECT AREA AND GENRE TO SEARCH.

SHINJYUKU  
SHIBUYA  
IKEBUKURO  
GINZA  
IKEBUKIRO

LARGE BUSINESS CATEGORIES

RESTAURANTS

STORES

COMPANIES

AMUSEMENT/  
SPORTS FACILITIES

SERVICES

PUBLIC FACILITIES/  
PUBLIC OFFICES

SEARCH

INPUT STORE/COMPANY NAME


SEARCH

*Fig. 16*

[illegible]

*Fig. 17A*


LINKING OPERATION WITH LINK BUTTON





*Fig. 17B*

ENLARGING/REDUCING OPERATION AND MOVING OPERATION BY USER



1000  
 900  
 800  
 700  
 600  
 500  
 400  
 300  
 200  
 100  
 0

**As a below-named inventor, I hereby declare that:**

**I believe I am the original, first and sole inventor (if only one name is listed below) or an original, first and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention entitled:**

**The specification of which  
(check one)**

\_\_\_\_\_ was filed on \_\_\_\_\_ as \_\_\_\_\_

and was amended on \_\_\_\_\_

**I hereby state that I have reviewed and understand the contents of the above-identified specification, including the claims, as amended by any amendment referred to above.**

**I hereby claim foreign priority benefits under Title 35, United States Code, Section 119 of any foreign application(s) for patent or inventor's certificate listed below and have also identified below any foreign application for patent or inventor's certificate having a filing date before that of the application on which priority is claimed:**

**Priority Claimed**

No

---

Declaration and Power of Attorney

Page 2

I hereby claim the benefit under Title 35, United States Code, Section 120 of any United States Application(s) listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States application in the manner provided by the first paragraph of Title 35, United States Code, Section 112, I acknowledge the duty to disclose material information as defined in Title 37, Code of Federal Regulations, Section 1.56(a) which occurred between the filing date of the prior application and the national or PCT international filing date of this application:

<u>Application Serial No.</u>	<u>Filing Date</u>	<u>Status</u>
_____	_____	_____
_____	_____	_____

And I hereby appoint Jay H. Maioli, Reg. No. 27,213; Donald S. Dowden, Reg. No. 20,701; William E. Pelton, Reg. No. 25,702; Peter J. Phillips, Reg. No. 29,691; Gerald W. Griffin, Reg. No. 18,886; Ivan S. Kavrukov, Reg. No. 25,161; Christopher C. Dunham, Reg. No. 22,031; Norman H. Zivin, Reg. No. 25,385; John P. White, Reg. No. 28,678; and Robert D. Katz, Reg. No. 30,141; and each and all of them, all c/o Cooper & Dunham, 1185 Avenue of the Americas, New York, NY 10036 (Tel. (212) 278-0400), my attorneys, each with full power of substitution and revocation, to receive the patent, to transact all business in the Patent and Trademark Office connected therewith and to file any International Applications which are based thereon under the provisions of the Patent Cooperation Treaty.

Please address all communications, and direct all telephone calls, regarding this application to

**JAY H. MAIOLI**  
Cooper & Dunham LLP  
1185 Avenue of the Americas  
New York, New York 10036  
Tel. (212) 278-0400

Reg. No. 27,213

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

Full name of sole or

First joint inventor Chiharu Hirono

Inventor's signature \_\_\_\_\_

Citizenship Japanese Date of Signature \_\_\_\_\_

Residence Tokyo, Japan

Post Office Address c/o Sony Corporation, 7-35 Kitashinagawa, 6-Chome,

Shinagawa-ku, Tokyo, Japan